

**OFFICIAL BID PROPOSAL**

2019-2 WATER SYSTEM IMPROVEMENTS  
ROSELAND DRIVE - 70<sup>TH</sup> STREET TO 64<sup>TH</sup> STREET  
URBANDALE WATER UTILITY  
URBANDALE, IOWA

Name of Bidder \_\_\_\_\_

Address of Bidder \_\_\_\_\_

To: Board of Trustees  
3720 86<sup>th</sup> Street  
Urbandale Water Utility  
Urbandale, Iowa 50322

The undersigned bidder submits herewith a bid security amounting to ten percent (10%) of the total amount of the bid, which shall become the property of the Urbandale Water Utility, should the undersigned fail or refuse to execute a contract and to furnish bond as called for in the specifications within the time provided.

The undersigned bidder, having examined the contract documents, and having familiarized himself/herself with the nature and location of the work to be done and the conditions under which the work will be performed, hereby proposes to provide the required labor, services and materials and to perform the work described in the specifications, and addendum \_\_\_\_\_, \_\_\_\_, \_\_\_\_ and \_\_\_\_, within the time and for the sum or sums stated hereinafter on attached proposal schedule which proposal schedule is hereby made a part of this proposal.

The undersigned bidder certifies that this proposal is made in good faith, without collusion or connection with any other person or persons bidding on this work.

The undersigned bidder states that this proposal is made in conformity with the specifications and agrees that the event of any discrepancies or differences between any conditions of his/her proposal and the specifications that the provisions of the latter shall prevail.

Bidder \_\_\_\_\_

By \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

**PROPOSAL SCHEDULE**

2019-2 WATER SYSTEM IMPROVEMENTS  
ROSELAND DRIVE - 70<sup>TH</sup> STREET TO 64<sup>TH</sup> STREET

1. Construct 2019-2 Water System Improvements, Roseland Drive - 70<sup>th</sup> Street to 64<sup>th</sup> Street, for the following lump sum prices:

<u>Description</u>	<u>Unit</u>	<u>Base Estimated Quantity</u>	<u>Unit Price</u>	<u>Extended Price</u>
1.1 Water Main in Place				
1.1.1 8" PVC	LF	1,939	_____	_____
1.2 Connections				
1.2.1 Connection #1, In the northeast corner of 70 <sup>th</sup> St. & Roseland Dr. Install 8" val., Connect to existing 8" main, aban 4" main.	LS	1	LS	_____
1.2.2 Connection #2, In the northwest corner of 68 <sup>th</sup> & Roseland Dr. Install 8" x 8" tee, 8" val., 8" x 6" red., 2 6" 45-deg. Bends. Connect to existing 6" main, aban. 6" main.	LS	1	LS	_____
1.2.3 Connection #3, In the northeast corner of 68 <sup>th</sup> & Roseland Dr. Install 8" x 8" tee, 8" val., 8" x 6" red., 2 6" 45-deg. Bends. Connect to existing 6" main, aban. 6" main.	LS	1	LS	_____
1.2.3 Connection #4, In the northwest corner of 66 <sup>th</sup> St. & Roseland Dr. Install 8" x 8" tee. Connect to existing 8" main, aban. 8" main.	LS	1	LS	_____
1.2.3 Connection #5, In the northwest 64 <sup>th</sup> St. & Roseland Dr. Connect to existing 8" main.	LS	1	LS	_____

**OFFICIAL BID PROPOSAL**

<u>Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Base Extended Price</u>
1.3 Hydrant Removal	Ea.	2	_____	_____
1.4 Hydrant Placement	Ea.	4	_____	_____
1.5 Water Service Connections				
1.5.1 1-Inch Near Side of Street With New Stop Box	Ea.	24	_____	_____
1.5.2 1-Inch Far Side of Street With New Stop Box	Ea.	20	_____	_____
1.5.3 2-Inch Near Side of Street With New Stop Box	Ea.	1	_____	_____
1.6 Surface Replacement				
1.6.1 Removal 6" Portland Cement Concrete Pavement	SY	50	_____	_____
1.6.2 7" Portland Cement Concrete Pavement	SY	60	_____	_____
1.6.3 Removal 6" Portland Cement Concrete Pavement with 2" Asphalt Overlay.	SY	70	_____	_____
1.6.4 7" Portland Cement Concrete Pavement with 2" Asphalt Overlay.	SY	60	_____	_____
1.6.5 5" Portland Cement Removal Concrete Driveway	SY	260	_____	_____
1.6.6 6" Portland Cement Concrete Driveway	SY	260	_____	_____
1.6.7 4" Sidewalk Removal	SY	284	_____	_____
1.6.8 6" Sidewalk	SY	28	_____	_____
1.6.9 4" Sidewalk	SY	256	_____	_____
1.6.10 ADA Pedestrian Ramp Dome	SF	90	_____	_____

**OFFICIAL BID PROPOSAL**

<u>Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Base Extended Price</u>
1.7 Survey	LS	1	LS	_____
1.8 Traffic Control and Early Signage	LS	1	LS	_____
			TOTAL BASE BID	\$_____

- 1 The work on this project shall begin construction on or after July 8, 2019 complete within ninety (90) calendar days with a completion date of October 11, 2019.
- 2 Liquidated damages in the amount of Five Hundred Dollars (\$500.00) per calendar day will be assessed for each day that work shall remain uncompleted after the end of the contract period, with due allowance for extensions of the contract period due to conditions beyond the control of Contractor.
- 3 The contractor shall provide all other materials to complete the project.