

2024-1 WATER SYSTEM IMPROVEMENTS  
MEREDITH DRIVE – 132<sup>ND</sup> STREET TO 142<sup>ND</sup> STREET  
URBANDALE WATER UTILITY  
URBANDALE, IOWA

Name of Bidder \_\_\_\_\_

Address of Bidder \_\_\_\_\_

To: Board of Trustees  
3720 86<sup>th</sup> Street  
Urbandale Water Utility  
Urbandale, Iowa 50322

The undersigned bidder submits herewith a bid security amounting to ten percent (10%) of the total amount of the bid, which shall become the property of the Urbandale Water Utility, should the undersigned fail or refuse to execute a contract and to furnish bond as called for in the specifications within the time provided.

The undersigned bidder, having examined the contract documents, and having familiarized himself/herself with the nature and location of the work to be done and the conditions under which the work will be performed, hereby proposes to provide the required labor, services and materials and to perform the work described in the specifications, and addendums, within the time and for the sum or sums stated hereinafter on attached proposal schedule which proposal schedule is hereby made a part of this proposal.

The undersigned bidder certifies that this proposal is made in good faith, without collusion or connection with any other person or persons bidding on this work.

The undersigned bidder states that this proposal is made in conformity with the specifications and agrees that the event of any discrepancies or differences between any conditions of his/her proposal and the specifications that the provisions of the latter shall prevail.

Bidder \_\_\_\_\_

By \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

**PROPOSAL SCHEDULE**

**2024-1 WATER SYSTEM IMPROVEMENTS  
MEREDITH DRIVE – 132<sup>ND</sup> STREET TO 142<sup>ND</sup> STREET**

ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	EXTENSION
1	WATER MAIN, PVC, TRENCHED, 16 IN. DIA.	LF	3545	\$	\$
2	WATER MAIN, CERTA-LOK PVC, TRENCHLESS, 16 IN. DIA.	LF	400	\$	\$
3	CONNECTION #1 – 142 <sup>ND</sup> STREET & MEREDITH DRIVE, STA. 0+00	LS	1	\$	\$
4	CONNECTION #2 – 132 <sup>ND</sup> STREET & MEREDITH DRIVE, STA. 39+50	LS	1	\$	\$
5	FIRE HYDRANT REMOVAL	EA	2	\$	\$
6	FIRE HYDRANT PLACEMENT	EA	8	\$	\$
7	VALVE, GATE, 16 IN. DIA.	EA	3	\$	\$
8	1 IN DIA. WATER SRVICE CONNECTION, FAR SIDE, ABANDON EX. TAP	EA	1	\$	\$
9	SIDEWALK PAVEMENT REMOVAL, PCC, 5 IN.	SY	15	\$	\$
10	SIDEWALK PAVEMENT REPLACEMENT, PCC, 6 IN..	SY	15	\$	\$
11	DRIVEWAY PAVEMENT REMOVAL, PCC, 5 IN.	SY	57	\$	\$
12	DRIVEWAY PAVEMENT REPLACEMENT, PCC, 6 IN.	SY	57	\$	\$
13	REINFORCVD STREET PAVEMENT REMOVAL, PCC, 8.25 IN.	SY	8	\$	\$
14	REINFORCED STREET PAVEMENT PLACEMENT, PCC, 9.25 IN.	SY	8	\$	\$
15	PORTLAND CEMENT CONCRETE CURB AND GUTTER, 6 IN.	LF	25	\$	\$
16	TEMPORARY TRAFFIC CONTROL	LS	1	\$	\$
17	UTILITY EXPLORATION AND LOCATION	LS	1	\$	\$
18	SITE RESTORATION/SEEDING	AC	0.8	\$	\$
19	EROSION CONTROL - HYDROMULCH	AC	0.8	\$	\$
20	DROP-IN INLET BASKET PROTECTION DEVICE	EA	15	\$	\$

## **PROPOSAL**

- 1 The work on this project shall begin construction on or before April 1, 2024 with a completion date of June 28, 2024.
- 2 Liquidated damages in the amount of Five Hundred Dollars (\$500.00) per calendar day will be assessed for each day that work shall remain uncompleted after the end of the contract period, with due allowance for extensions of the contract period due to conditions beyond the control of Contractor.
- 3 The contractor shall provide all other materials to complete the project.